

**Engineers, Planners & Landscape Architects** 

#### **Engineering**

Land/Site Development

Municipal Infrastructure

Environmental/ Water Resources

Traffic/

Transportation

Recreational

#### **Planning**

Land/Site Development

Planning Application Management

**Municipal Planning** 

Urban Design

Expert Witness (LPAT)

Wireless Industry

#### Landscape Architecture

Streetscapes & Public Amenities

Open Space, Parks &

Recreation

Community & Residential

Commercial & Institutional

Environmental

Restoration

**Hannan Hills** 

Serviceability and Conceptual Stormwater Management Report



Prepared for: 1384341 Ontario Ltd

## SERVICEABILITY AND CONCEPTUAL STORMWATER MANAGEMENT REPORT

## In support of Draft Plan of Subdivision And Zoning By-law Amendment Applications

# Hannan Hills Residential Development Almonte, ON

Prepared For:





Prepared By:

NOVATECH Suite 200, 240 Michael Cowpland Drive Ottawa, Ontario K2M 1P6

> May 2021 Novatech File: 118201

> > Ref: R-2021-010



May 20, 2021 BY COURIER

County of Lanark Planning Department 99 Christie Lake Road Perth, ON K7H 3C6

Attention: Julie Stewart, RPP, MCIP County Planner

Reference: Hannan Hills Residential Development

Serviceability and Conceptual Stormwater Management Report

Our File No.: 118201

Please find enclosed the report entitled "Serviceability and Conceptual Stormwater Management Report" dated May 20, 2021 prepared for the Hannan Hills Residential Development.

The report outlines the preliminary servicing design for the proposed development with respect to water distribution, sanitary servicing and storm drainage, as well as a preliminary approach to stormwater management. This report is submitted in support of an application for Draft Plan Approval.

If you require any additional information, please contact the undersigned

Yours truly,

**NOVATECH** 

Alex McAuley, P. Eng.

Project Manager | Land Development Engineering

cc: Robert Dick, Douglas McIntosh, Neilcorp Homes

Matt Nesrallah, Cavanagh Construction

## **Table of Contents**

1.0	IN	ITRODUCTION
1.1		Purpose
1.2	;	Site Location and Description
1.3		Proposed Development
2.0	RC	OAD DESIGN2
3.0	SI	ITE SERVICING2
3.1	,	Watermain
3.2	;	Sanitary Sewer
3.3	;	Storm Drainage
3	3.3.	1 Storm Sewers (Minor System)
3	3.3.2	2 Major System Drainage
4.0	ST	TORMWATER MANAGEMENT
4	!.1.	1 Quality Control
4	1.1.2	2 Quantity Control
4	1.1.3	3 Best Management Practices and Low Impact Development
5.0	EF	ROSION AND SEDIMENT CONTROL6
5.1	•	Temporary Measures6
5.2	ļ	Permanent Measures
6.0	CC	ONCLUSIONS AND RECOMMENDATIONS
	2: 2: 3: 4: 5:	Concept Plan Watermain Servicing Sanitary Servicing

#### **List of Tables**

Table 3.1 J.L. Richards Master Plan Update Report – Honeyborne Watermain

Figure 7: Conceptual Stormwater Management Facility

#### **List of Appendices**

Appendix A Correspondence
Appendix B Watermain Design
Appendix C Sanitary Sewer Design
Appendix D Storm Sewer Design
Appendix E Conceptual Stormwater Management Design Memo
Appendix F Excerpts from J.L. Richards Master Plan Update Report – February 2018

#### **List of Drawings**

Draft Plan of Subdivision (AOV) 118201-PGR Preliminary Grading and Servicing Plan

Novatech Page ii

#### 1.0 INTRODUCTION

Novatech has been retained to prepare a serviceability and conceptual stormwater management report in support of an application for Draft Plan Approval for the proposed Hannan Hills Residential Subdivision.

#### 1.1 Purpose

This report outlines the conceptual servicing design for the proposed development with respect to water distribution, sanitary servicing and storm drainage, as well as the approach to stormwater management.

#### 1.2 Site Location and Description

The property, approximately 4.15 hectares (10.3 acres) in size, is bound by undeveloped lands to the north with existing residential lands to the south, east and west. In addition, the Almonte Municipal Drain runs adjacent to the east property boundary. Refer to **Figure 1 (Key Plan)** for the site location.

The site is currently occupied by a single-family home and is lightly treed. Refer to **Figure 2** (**Existing Conditions Plan**) for an aerial photograph of the property.

#### 1.3 Proposed Development

It is proposed to develop a residential subdivision of 166 townhomes with the following unit breakdown:

Unit Type	Number of Units
2-Storey Street Facing Townhome	78
Stacked Townhome	48
Back-to-Back Townhome	40

The development will include one new road as well as an extension of Adelaide Street that will connect to Honeyborne Street. Refer to **Preliminary Grading and Servicing Plan (118201-PGR)** and **Figure 3 (Concept Plan)** for the conceptual site layout.

Connections will be made to the existing Mill Run Subdivision to the east via the Adelaide Street extension to Honeyborne Street, and to Florence Street to the west. Refer to the **Draft Plan of Subdivision** for a detailed layout of the proposed subdivision.

Blocks for the stacked townhomes and back-to-back townhomes would be subject to site plan approval.

The proposed development and its impact on the existing surrounding infrastructure has been examined in a previous report by J.L. Richards (J.L. Richards Master Plan Update Report – February 2018) in which assumptions of future buildout within the town of Almonte have been made, along with recommendations on upgrades to existing infrastructure. This report references the J.L. Richards report throughout, and relevant excerpts are provided in **Appendix F**.

#### 2.0 ROAD DESIGN

The internal subdivision roads will be constructed in accordance with the typical road cross-sections as shown on the **Preliminary Grading and Servicing Plan** (118201-PGR). The proposed 18-metre right-of-way will have an 8.5-metre asphalt width and curbs with no sidewalks. Upgrades to the existing municipal road allowances for Florence and Adelaide will be required. Based on required road-widenings and existing conditions, the municipal road cross sections will need to be determined at the detailed design stage.

The pavement structure will be confirmed based on a geotechnical recommendation during the detailed design stage.

#### 3.0 SITE SERVICING

#### 3.1 Watermain

Refer to Figure 4 (Watermain Servicing) for preliminary watermain layout.

The proposed 250mm and 200mm watermain to service the lots within the subdivision will connect to the existing 250mm watermain on Honeyborne Street (to the east), and to the existing 150mm watermain on Adelaide Street at Finner Court (to the west).

Fire hydrants will be installed along the proposed streets to provide fire protection. Preliminary Ontario Building Code (OBC) fire flow calculations indicate required fire flows between 45L/s and 90L/s. Addition of firewalls may be considered to reduce the higher end flow of 90L/s. Further analysis of required fire flow and potential firewall implementation would be completed at the detailed design stage. Fire flow calculations are provided in **Appendix B.** 

Based on a review of the J.L. Richards Master Plan Update Report – February 2018 (2018 Master Report), the development can be adequately serviced. Initial review indicates that fire flow can be provided, and that pressure reducing valves may be required. Refer to **Appendix F** for excerpts from the 2018 Master Report.

The pressures and flows available as indicated in the 2018 Master Report are summarized in Table 3.1 below. All values below have been taken from J.L. Richards Figures 7-16 in **Appendix F**.

Table 3.1: J.L. Richards Master Plan Update Report – Honeyborne Watermain

Time Period	Peak Hour	Max. Day + Fire	Figure #
	Pressure (kPa)	Flow (L/s)	
Existing	401-550	100-300	7,8
2018-2022 (With Mill Run			
buildout)	401-550	100-300	9,10
2023-2028 (With subject			
lands developed)	301-400	100-300	11,12
2037+ (With future			
development to the north)	<274	68-75	15,16

Confirmation of existing flow conditions and a hydraulic network analysis of the proposed watermain layout would be completed at the detailed design stage.

#### 3.2 Sanitary Sewer

Refer to Figure 5 (Sanitary Servicing) for preliminary sanitary sewer layout.

New 200mm diameter sanitary sewers will service the proposed development. The sewage flows from the site will be directed by gravity and connect to the proposed 300mm sewer located on Florence Street which will tie into the existing sanitary trunk sewer at Victoria Street. The trunk sewer ultimately conveys the flows to the Gemmill Bay Pump Station, which pumps to the Town of Mississippi Mills Wastewater Treatment Plant (WWTP).

The design criteria used to determine the size of the sanitary sewers required to service the subdivision are as follows:

#### Residential Areas

Average flow - residential = 350 L/cap/day

Population for townhouse unit = 3.5 Residential Peaking factor based on the Harmon Formula = 4

The theoretical peak flow for the proposed subdivision was calculated to be in the order of 10.7 L/s. Refer to the enclosed **Preliminary Sanitary Drainage Area Plan (118201-PSAN)** and the Sanitary Sewer Design Sheet provided in **Appendix C** for details. The proposed sanitary sewer system will have sufficient capacity to convey the theoretical sanitary flows from the subdivision.

The proposed 300mm sanitary sewer on Florence Street has been sized to capture future additional flows from the undeveloped land to the north ("Development Area 2" of J.L. Richards Figure 25), and future infill property south of the site. Allocated flows provided in the Master Report have been considered in the design of the affected downstream sanitary sewers. Refer to J.L. Richards Figure 25 in **Appendix F** for location and allocated flows of the future buildout.

#### 3.3 Storm Drainage

Refer to Figure 6 (Storm Servicing) for preliminary storm sewer layout.

Storm drainage, both the minor and major systems, will outlet to a proposed stormwater management facility along the east side of the development. The stormwater management facility would provide quantity and quality control prior to discharging to the Almonte Municipal Drain. Quantity control would be provided by a dry pond. Quality control would be provided by a hydrodynamic separator unit.

#### 3.3.1 Storm Sewers (Minor System)

The proposed storm sewers have been designed using the Rational Method to convey peak flows associated with a 5-year return period.

Refer to the **Preliminary Storm Drainage Area Plan (118201-PSTM**) and the Storm Sewer Design Sheet provided in **Appendix D** for details.

#### Storm Sewer Design Criteria

The following is the storm sewer design criteria were used:

- Rational Method (Q) = 2.78CIA, where
  - Q = peak flow (L/s)
  - C = runoff coefficient

$$\circ$$
 C = (0.70 \* %lmp.) + 0.20

- I = rainfall intensity for a 2-year return period (mm/hr)
  - o  $I_{5yr} = 998.071 / [(Tc(min) + 6.053)]^{0.814}$
- A = site area (ha)
- Minimum Pipe Size = 250 mm; Minimum / Maximum Full Flow Velocity = 0.8 m/s / 3.0 m/s

#### Inlet Control Devices

Inlet control devices (ICDs) will be used to restrict inflows to the minor system. Rear yard catch basins will be connected in series with an ICD installed at the outlet of the most downstream structure. ICDs will be sized to control minor system peak flows without causing surface ponding during a 5-year storm event.

#### Foundation Drains

Foundation drains surrounding the dwellings would be connected to the storm sewers. Based on the preliminary review of the hydraulic grade line, sump pumps would be required to drain the foundations. The sump pumps would connect to the storm sewer and would include backwater valves to prevent basement flooding in heavy rain events.

#### 3.3.2 Major System Drainage

During detailed design, the site will be graded to provide an overland flow route to a proposed dry pond following the proposed roadway. The proposed storm sewer system would direct all minor storm runoff to the proposed Stormwater Management (SWM) Facility. Runoff from the major system would be directed overland to the same facility. The SWM Facility will be designed to provide stormwater quality and quantity control prior to outletting to the Almonte Municipal Drain.

#### 4.0 STORMWATER MANAGEMENT

Refer to **Figure 7 (Conceptual Stormwater Management Facility)** for preliminary Stormwater Management Facility design. Supporting calculations are provided in the Conceptual Stormwater Management Design Memo in **Appendix E.** 

All storm runoff (major and minor systems) from the proposed development will be directed to the proposed Stormwater Management Facility.

#### 4.1.1 Quality Control

Water quality treatment will be provided by the SWM Facility. A water quality treatment unit is required as part of the proposed subdivision works to remove debris and sediment prior to discharging to the SWM Facility. A hydrodynamic separator (HDS) would be appropriately sized to meet this requirement and would be installed just upstream of the subdivision's outlet to the

SWM Facility. Supporting calculations are provided in the Conceptual Stormwater Management Design Memo in **Appendix E.** The HDS would be located within the SWM Facility block and would be accessible from the SWM Facility for inspection and maintenance. In addition, the SWM Facility will be able to provide a 24 hour draw down time and a low flow channel to supplement the total suspended solids removal of the HDS. The HDS unit and size would be confirmed at detailed design.

#### 4.1.2 Quantity Control

Quantity control of peak flows to pre-development levels will be required. Flows entering the minor system will be controlled to the design capacity of the sewers. Peak flows from larger storm events may be stored in the rights-of-way and will be conveyed overland to the SWM Facility along the rights-of-way which will provide sufficient capacity to convey runoff from all storms up to and including the 100-year design event. Refer to **Appendix E** for the Conceptual Stormwater Management Design Memo detailing the conceptual stormwater management approach.

#### 4.1.3 Best Management Practices and Low Impact Development

The proposed development will use the following stormwater best management practices (BMPs) and low impact development (LID) techniques to mitigate the reduction in groundwater infiltration/recharge resulting from development:

- Rearyard CB leads will use perforated pipes to promote infiltration of runoff from rearyard areas.
- Roof leaders should be directed to rearyard areas.
- A review of pre and post-development water balance (infiltration, runoff, and evaporation)
  would be included in the detailed design stage. The water balance would include
  recommendations to meet pre-development infiltration rates. These measures may
  include infiltration trenches, rearyard subdrains, etc. and will be confirmed at the detailed
  design stage.

By implementing stormwater management BMPs and LIDs as part of the storm drainage design, the impacts of development on the hydrologic cycle can be reduced. Infiltration of clean runoff provides additional benefits: The performance of the proposed hydrodynamic separator unit would be improved, and the storage required in the SWM Facility would be reduced. At the conceptual design stage, the use of BMPs and LIDs have not been included in the SWM calculations to provide a conservative estimate of the runoff volumes and storage requirements.

The use and implementation of BMPs and LIDs will be reviewed again during the detailed design process.

#### 5.0 EROSION AND SEDIMENT CONTROL

#### 5.1 Temporary Measures

The following erosion and sediment control measures will be implemented during construction in accordance with the "Guidelines on Erosion and Sediment Control for Urban Construction Sites" (Government of Ontario, May 1987).

To mitigate erosion and to prevent sediment from entering the storm sewer system, temporary erosion and sediment control measures will be implemented on-site during construction in accordance with the Best Management Practices for Erosion and Sediment Control. This includes the following temporary measures:

- Sediment control bags will be placed under the grates of on-site and nearby catchbasins and manholes and will remain in place until vegetation has been established and construction is completed;
- Silt fencing will be placed around the construction limits;
- Straw bale barriers and/or rock flow check dams will be placed within any drainage ditches until vegetation has been established and construction is completed;
- Street sweeping and cleaning will be performed as required to suppress dust and to provide safe and clean roadways adjacent to the construction site;
- Minimize the extent of exposed soil during construction and re-establish vegetation as soon as possible; and
- After construction is complete, all sewers are to be inspected and cleaned.

The proposed temporary erosion and sediment control measures would be implemented prior to construction remain in place throughout each phase of construction and should be inspected regularly. No control measure is to be permanently removed without prior authorization from the Engineer.

#### 5.2 Permanent Measures

The following will provide permanent erosion and sediment control measures:

- Grass swales along the rear and side yard property lines;
- The hydrodynamic separator unit will be designed to provide quality control for stormwater runoff prior to entering the SWMF.
- Rearyard drainage systems would be designed with a perforated pipe and clearstone to promote infiltration.
- Slopes on finish lot grades would be minimized where possible to slow the runoff of water.

#### 6.0 CONCLUSIONS AND RECOMMENDATIONS

This report has been prepared in support of an application for Draft Plan Approval for the proposed Hannan Hills Residential Subdivision.

- The development will be serviced by connecting to existing watermains in the adjacent subdivisions.
- The development will be serviced by connecting sanitary sewers to the existing trunk sewer on Victoria Street.
- Stormwater runoff from the site will be captured by an onsite storm sewer system via a series of rear-yard swales and roadside catchbasins. The storm sewer system will direct runoff to a Stormwater Management Facility prior to releasing flows to the Almonte Municipal Drain.
- Quantity control of stormwater runoff will be provided by the Stormwater Management Facility (Dry Pond).
- Quality control of stormwater runoff will be provided by the Stormwater Management Facility which will include the hydrodynamic separator, a 24-hour draw down time, and a low flow channel.
- Temporary and permanent erosion and sediment control measures will be provided.
- Subdivision would be designed in accordance with the J.L. Richards Master Plan Update Report – February 2018

**NOVATECH** 

Prepared by:

Prepared by:

Alex McAuley, P.Eng.
Project Manager | Land Development


100141256 (au 20.20

Mitch Parker, B. Eng.


Reviewed by:

Susan Gordon, P.Eng., MBA Director | Land Development


S.M. GORDON TO May 20/21





SHT8X11.DWG - 216mmx279mm





CUTAIVAZ DIVIC 270mm V422m











## APPENDIX A Correspondence



## Pre-Consultation Meeting Notes Virtual zoom meeting – January 27, 2021

Prepared By: Julie Stewart

#### In Attendance

Steve Pentz – Senior Project Manager, Novatech

John Riddell - Regional Group

Susan Gordon – Novatech

Matt Nesrallah – Cavanagh Construction

Robert Dick - Neilcorp

Maggie Yet – Junior Planner, Mississippi Mills

Marc Rivet - Planner, JL Richards - Mississippi Mills

Ken Kelly – CAO, Mississippi Mills

Cory Smith - Public Works, Mississippi Mills

Matt Craig - Planner, MVCA

Kelly Stiles - Biologist, MVCA

Diane Reid - Environmental Planner, MVCA

Julie Stewart - County Planner, County of Lanark

Steve Pentz provided a brief background.

Official Plan Designation – Residential

Zoning – Development Reserve

- Proposing an 18 m right of way
- Mix of townhouses and semi-detached total of 96 units
- Units designed to accommodate the market need of the municipality family friendly, and price points
- Propose a 15m setback from the wetland

9 metre easement on subject property which is an existing Drainage Easement in favour of the Town

**Planning Report** – density to be addressed within.

#### **Environmental Impact Study**

MVCA spoke to background and requirements.

Matt provided background on the conservation authorities wetlands policies from 2019 and the consultation at that time.

Following the meeting notes were provided by MVCA and are included below:

#### **Planning**

- We will need to review the SW Plan and EIS.
- Components of this plan should include any mitigation from the results of the HIS & EIS and impacts to the function of the wetland on site.
- Lot orientation and layout seem predetermined prior to submission of an EIS, should include LID

MVCA and the Township have recommended that the SW pond be located on the NE corner of the site, if not possible then these lands may need to remain undeveloped to provide adequate buffer to wetlands to the north.

#### **MVCA** Requirements

- Hydrologic Impact Assessment and EIS (concurrent with planning requirements) as it relates to the SW requirements - what are the results of development on the adjacent watercourse, water table and wetlands? The report should include mitigation and offsetting recommendations to address the loss of wetland on site.
- Organic material must be removed from the site.
- Permits required for the development as in regulated area and out letting to any watercourse.

#### **Servicing Options Statement**

- As the site is will be on public services, a Conceptual Servicing Report shall be submitted with the application.

#### **Stormwater Drainage Plan**

- MVCA advised that Stormwater Management, Quality and Quantity control would be required, with Quality to an enhanced level of treatment 80%.
- Reference was made to water balance

#### Traffic Study

- The Municipality advised that a traffic study will be required to address connection to municipal streets and the increase in traffic.

#### **OTHER**

## **Geotechnical Report –** required

### **Environmental Site Assessment**

- The developer indicated that an ESA has been prepared.

Please refer to the attached Pre-Consultation Checklist as well as the itemized items above.

APPENDIX B
Watermain Design



## HANNAN HILLS SUBDIVISION Preliminary Demands

	Wa	iter Demai	nd Calcul	ati	ons			
		Demand (L/s	)					
Node	Ur	nits	Total					
Node	Townhouse (row)	Townhouse (stacked)	Population		Avg Day	Max. Daily	Peak Hour	
Street One (Freeholds)	78		211		0.85	2.14	4.70	
Adelaide (Back-to-back)	40		108		0.44	1.09	2.41	
Adelaide (stacked)		48	130		0.53	1.32	2.90	
Total	118	48	449		1.82	4.55	10.00	

#### Notes:

Residential Densities (from City of Ottawa data):

- Townhouse/Semi Detached =		2.	.7	cap/unit
Avg. Daily Demand:				
- Residential	=	35	50	L/cap/day
Max. Daily Demand:				
- Residential	=	2.	.5	x Avg. Day
Peak Hourly Demand:				
- Residential	=	2.	.2	x Max. Day

Based on OBC 2012 (Div. B, Article 3.2.5.7)

References: Ontario Fire Marshal - OBC Fire Fighting Water Supply

Ontario Building Code 2012, Appendix A, Vol 2., A-3.2.5.7

Novatech Project #: 118201
Project Name: Hannan Hills

Date: 5/13/2021
Input By: M.Parker
Reviewed By: A.McAuley

Building Description: Back-to-back 8 Unit Townhome

Unsprinklered



Legend
Input by User
No Input Required

		Calculation I	nputs	Calculation	on Notes		Value	
	Minimu	m Fire Prot	ection	Water Supply Vo	olume			
	Water Supply Coefficient							
1	Building Classification =	С		From Tabl	e 3.1.2.1			
	Water Supply Coefficient - K =			From Table 1	(A3.2.5.7)		23	
	Total Building Volume							
	Building Width - W	25.50	m					
2	Building Length - L	18.30	m	Area (W * L) =	467 m2			
	Building Height - H	9.2	m					
	Total Building Volume - V =			W * L	. * H		4293 m	13
	Spatial Coefficient Value					=		
	Exposure Distances:			<b>Spatial Coefficients</b>	:			
	(Exterior building face to property/lot li or to mid-point between proposed buil building on same lot)			From Figure 1 (Spa Exposure [				
3	North	6.10	m	Sside 1 =	0.39			
	East	15.30	m	Sside 2 =	0.00			
	South	1.20	m	Sside 3 =	0.50			
	West	9.70	m	Sside 4 =	0.03			
	Total of Spacial Coefficient Values as obtained from the formula =	- S-Tot		1.0 + (Sside 1 + Ss Sside 4) (Max	side 2 + Sside 3 + x. value = 2.0)		1.92	
4	Minimum Fire Protection Water Sup	ply Volume						
7	Q =			K * V *	S <sub>Tot</sub>	1	89,587	L
	Re	equired Mir	nimum	Water Supply Fl	ow Rate			
	Minimum Water Supply Flow Rate			From Table 2 (For w			5,400	L/min
5	=			municipal or indust	11,	or	90 L	
	Minimum E	iro Protocti	ion W	system, min. presenter Supply Volun	,		30 L	-
	I I I I I I I I I I I I I I I I I I I	ire Protecti	OII W			25		
6	Q =			= Minimum Water S (L/min) * 30		1	62,000 L	
	Rec	uired Fire	Protec	tion Water Suppl	ly Volume			
7	Q =			Highest volume o	ut of (4) and (6)	1	89,587 L	
Notes								

Based on OBC 2012 (Div. B, Article 3.2.5.7)

References: Ontario Fire Marshal - OBC Fire Fighting Water Supply

Ontario Building Code 2012, Appendix A, Vol 2., A-3.2.5.7

Novatech Project #: 118201
Project Name: Hannan Hills

Date: 5/13/2021
Input By: M.Parker
Reviewed By: A.McAuley

Building Description: Back-to-back 12 Unit Townhome

Unsprinklered



Legend
Input by User
No Input Required

Step		Calculation I	nputs	Calculation Notes	Value
	Minimu	m Fire Prot	ection	Water Supply Volume	
	Water Supply Coefficient				
1	Building Classification = Water Supply Coefficient - K =	С		From Table 3.1.2.1 From Table 1 (A3.2.5.7)	23
	Total Building Volume				20
	Building Width - W	38.40	m		
2	Building Length - L	18.30	m	Area (W * L) = 703 m2	
	Building Height - H	9.2	m	7.100 (1.1 2)	
	Total Building Volume - V =			W * L * H	6465 m³
	Spatial Coefficient Value			1	
	Exposure Distances:			Spatial Coefficients:	
	(Exterior building face to property/lot li or to mid-point between proposed buil- building on same lot)			From Figure 1 (Spatial Coefficient vs Exposure Distance)	
3	North	9.20	m	Sside 1 = <b>0.08</b>	
	East	10.10	m	Sside 2 = <b>0.00</b>	
	South	14.90	m	Sside 3 = <b>0.00</b>	
	West	10.50	m	Sside 4 = <b>0.00</b>	
	Total of Spacial Coefficient Values as obtained from the formula =	- S-Tot		1.0 + (Sside 1 + Sside 2 + Sside 3 + Sside 4) (Max. value = 2.0)	1.08
4	Minimum Fire Protection Water Sup	ply Volume			
4	Q =			K * V * S <sub>Tot</sub>	160,591 L
	Re	equired Mir	nimum	Water Supply Flow Rate	
5	Minimum Water Supply Flow Rate =			From Table 2 (For water supply from a municipal or industrial water supply system, min. pressure is 140 kPa)	4,500 L/min
	Minimum F	ire Protecti	on Wa	ater Supply Volume for 30 minu	ites
6	Q =			= Minimum Water Supply Flow Rate (L/min) * 30 minutes	135,000 L
	Rec	uired Fire	Protec	tion Water Supply Volume	•
7	Q =			Highest volume out of (4) and (6)	160,591 L
Notes					

Based on OBC 2012 (Div. B, Article 3.2.5.7)

References: Ontario Fire Marshal - OBC Fire Fighting Water Supply

Ontario Building Code 2012, Appendix A, Vol 2., A-3.2.5.7

Novatech Project #: 118201
Project Name: Evoy

Date: 5/13/2021
Input By: M.Parker
Reviewed By: A.McAuley

**Building Description: Stacked-8 Unit Townhome** 

Unsprinklered



Legend
Input by User
No Input Required

Step		Calculation I	nputs	Calculation	Notes	Value	
	Minimu	m Fire Prot	ection	n Water Supply Vol	ume		
	Water Supply Coefficient						
1	Building Classification = Water Supply Coefficient - K =	С		From Table From Table 1	23		
	Total Building Volume						
	Building Width - W	19.80	m				
2	Building Length - L	13.00	m	Area (W * L) =	257 m2		
	Building Height - H	15.2	m				
	Total Building Volume - V =			W * L *	Н	3912	m³
	Spatial Coefficient Value					=	
	Exposure Distances:			Spatial Coefficients:			
	(Exterior building face to property/lot li or to mid-point between proposed buil building on same lot)			From Figure 1 (Spatia Exposure Dis			
3	North	13.50	m	Sside 1 =	0.00		
	East	1.50	m	Sside 2 =	0.50		
	South	17.00	m	Sside 3 =	0.00		
	West	1.50	m	Sside 4 =	0.50		
	Total of Spacial Coefficient Values as obtained from the formula =	- S-Tot		1.0 + (Sside 1 + Ssid Sside 4) (Max.	e 2 + Sside 3 + value = 2.0)	2.00	
4	Minimum Fire Protection Water Sup	ply Volume					
4	Q =			K * V * S	Tot	179,974	L
	Ro	equired Mir	nimum	Water Supply Flor	w Rate		
5	Minimum Water Supply Flow Rate =			From Table 2 (For wat municipal or industrial system, min. pressu	al water supply	3,400	L/min L/s
	Minimum F	ire Protecti	on Wa	ater Supply Volume		es	
6	Q =			= Minimum Water Su (L/min) * 30 r	ipply Flow Rate	162,000	L
	Rec	uired Fire	Protec	tion Water Supply	Volume	•	
7	Q =			Highest volume out	of (4) and (6)	179,974	L
Notes							

Based on OBC 2012 (Div. B, Article 3.2.5.7)

References: Ontario Fire Marshal - OBC Fire Fighting Water Supply

Ontario Building Code 2012, Appendix A, Vol 2., A-3.2.5.7

Novatech Project #: 118201
Project Name: Evoy

Date: 5/13/2021
Input By: M.Parker
Reviewed By: A.McAuley

**Building Description: Street Facing 4 Unit Townhome** 

Unsprinklered



Input by User
No Input Required

Step		Calculation I	nputs	Calculation Notes	Value
	Minimu	m Fire Prot	ectior	Nater Supply Volume	
	Water Supply Coefficient				
1	Building Classification =	С		From Table 3.1.2.1	
	Water Supply Coefficient - K =			From Table 1 (A3.2.5.7)	23
	Total Building Volume				
	Building Width - W	20.90	m		
2	Building Length - L	14.30	m	Area (W * L) = 299 m2	
	Building Height - H	9.2	m		
	Total Building Volume - V =			W * L * H	2750 m³
	Spatial Coefficient Value				
	Exposure Distances:			Spatial Coefficients:	
	(Exterior building face to property/lot li			From Figure 1 (Spatial Coefficient vs	
	or to mid-point between proposed buil building on same lot)	ding and anoth	ner	Exposure Distance)	
3	North	15.60	m	Sside 1 = <b>0.00</b>	=
3	East	1.20	m	Sside 2 = <b>0.50</b>	
	South	7.60	m	Sside 3 = <b>0.24</b>	
	West	1.20	m	Sside 4 = <b>0.50</b>	
	Total of Spacial Coefficient Values	- S-Tot		1.0 + (Sside 1 + Sside 2 + Sside 3 +	2.00
	as obtained from the formula =			Sside 4) (Max. value = 2.0)	2.00
4	Minimum Fire Protection Water Sup	ply Volume			
4	Q =			K * V * S <sub>Tot</sub>	126,482 L
	R	equired Mir	imum	Water Supply Flow Rate	
	Minimum Water Supply Flow Rate			From Table 2 (For water supply from a	3,600 L/min
5	=			municipal or industrial water supply	or <b>60 L/s</b>
	Minimum F	iro Drotooti	an \4/a	system, min. pressure is 140 kPa)	
	Winimum F	ire Protecti	on wa	ater Supply Volume for 30 minu	ies T
6	Q =			= Minimum Water Supply Flow Rate (L/min) * 30 minutes	108,000 L
	Pos	univad Fira I	Drotos	, ,	
	rec I	quirea Fire	Protec	ction Water Supply Volume	
7	Q =			Highest volume out of (4) and (6)	126,482 L
Notes					
.10103					

Based on OBC 2012 (Div. B, Article 3.2.5.7)

References: Ontario Fire Marshal - OBC Fire Fighting Water Supply

Ontario Building Code 2012, Appendix A, Vol 2., A-3.2.5.7

Novatech Project #: 118201 Project Name: Hannan Hills

Date: 5/13/2021
Input By: M.Parker
Reviewed By: A.McAuley

**Building Description: Street Facing 6 Unit Townhome** 

Unsprinklered



Input by User
No Input Required

Step	I	Calculation I	nputs	Calculatio	n Notes	Val	ue
-	Minimu	m Fire Prot	tection	Water Supply Vo	olume		
	Water Supply Coefficient						
1	Building Classification =	С		From Table	e 3.1.2.1		
	Water Supply Coefficient - K =			From Table 1	(A3.2.5.7)		23
	Total Building Volume						
	Building Width - W	31.30	m				
2	Building Length - L	14.30	m	Area (W * L) =	448 m2		
	Building Height - H	9.2	m				
	Total Building Volume - V =			W * L	.* H	41	18 m³
	Spatial Coefficient Value					-	
	Exposure Distances:			Spatial Coefficients	:		
	(Exterior building face to property/lot lor to mid-point between proposed buil building on same lot)			From Figure 1 (Spa Exposure D			
3	North	16.30	m	Sside 1 =	0.00		
	East	1.20	m	Sside 2 =	0.50		
	South	15.40	m	Sside 3 =	0.00		
	West	1.20	m	Sside 4 =	0.50		
	Total of Spacial Coefficient Values as obtained from the formula =	- S-Tot		1.0 + (Sside 1 + Ss Sside 4) (Max	ide 2 + Sside 3 + x. value = 2.0)	2.0	00
4	Minimum Fire Protection Water Sup	ply Volume					
-	Q =			K * V *	S <sub>Tot</sub>	189,4	20 L
	R	equired Mir	nimum	Water Supply Flo	ow Rate		
5	Minimum Water Supply Flow Rate			From Table 2 (For w	trial water supply	<b>5,4</b> 0	00 L/min 90 L/s
	Minimum F	iro Protoct	ion W	system, min. press	,		50 L/3
	I William I	ile Frotect	011 ***	= Minimum Water S		-5	
6	Q =			= Minimum Water 8 (L/min) * 30		162,0	00 L
	Red	quired Fire	Protec	tion Water Suppl	y Volume		
7	Q =			Highest volume or	ut of (4) and (6)	189,4	20 L
Notes							

APPENDIX C
Sanitary Sewer Design

## **SANITARY SEWER DESIGN SHEET**

PROJECT: Hannan Hills Subdivision

PROJECT #: 118201 DESIGNED BY: MNP CHECKED BY: ARM DATE: May 13, 2021




	STREET	MAN	HOLE	INVERTS		UNITS		INDIVIE	DUAL	CUMUL	ATIVE	PEAK	POPULATION FLOW	PEAK EXTRAN.	PEAK DESIGN			F	PROPOSED SE	WER				
AREA ID	NAME	FROM	ТО	UPS DW	VS SINGLES/SEMI	APARTMENT	TOWNS	Population (thousands)	AREA (ha.)	Population (thousands)	AREA (ha.)	FACTOR M	Q (p) (L/s)	FLOW Q(i) (L/s)	FLOW Q(d) (L/s)	LENGTH (m)	PIPE SIZE (mm)	TYPE OF PIPE	GRADE %	CAPACITY (L/s)	FULL FLOW VELOCITY (m/s)	% OF CAPACITY (q <sub>full</sub> /Q <sub>actual)</sub>	% OF VELOCITY (V <sub>full</sub> /V <sub>actual)</sub>	ACUTAL VELOCITY (m/s)
D (Future by Others)	STREET 2	-	1		0	0	113	0.396	2.86	0.396	2.86	4.0	6.4	0.80	7.25	336.0	200.0	PVC	2.0	48.4	1.5	15%	70%	1.04
	*Note Assumed popu	lation base	ed on are	as A,B,C unit	density																			
A (Site)	STREET 1	-	2		0	0	78	0.273	2.68	0.273	2.68	4.0	4.4	0.75	5.17	288.0	200.0	PVC	2.0	48.4	1.5	11%	64%	0.95
B (Site)	ADELAIDE	-	1		0	0	40	0.140	1.03	0.140	1.03	4.0	2.3	0.29	2.56	90.0	200.0	PVC	0.5	24.2	0.7	11%	64%	0.48
C (Site)	ADELAIDE	1	3		0	0	48	0.168	0.80	0.704	4.69	3.9	11.1	1.31	12.41	126.0	200.0	PVC	0.5	24.2	0.7	51%	100%	0.75
E	FUTURE DEVELOPMENT	-	2		0	0	577	2.020	40.10	2.020	40.10	3.6	29.3	11.23	40.54	-	300.0	PVC	0.5	71.3	1.0	57%	103%	1.01
F	FLORENCE	2	3		0	0	0	0.000	0.19	2.293	42.97	3.5	32.9	12.03	44.90	77.0	300.0	PVC	0.5	71.3	1.0	63%	104%	1.02
G	FLORENCE	3	4		0	0	0	0.000	0.24	2.996	47.90	3.4	41.8	13.41	55.20	203.0	300.0	PVC	0.5	71.3	1.0	77%	108%	1.06
	*NOTE Existing 200m	ım sanitar	y on Flore	ence between	Maude and Victori	a to be upgra	ided																	
H (Future Infill by Others)	MCDERMOTT	-	4		5	0	3	0.030	1.32	0.030	1.32	4.0	0.5	0.37	0.85	203.0	300.0	PVC	0.5	71.3	1.0	1%	33%	0.32
	**NOTE Assumed po	pulaion ba	sed on th	e allocated flo	ow from the 2018 M	laster Report	on a L/s/	ha basis (5.9	7L/s over	9.5ha = 0.6	3L/s/ha)													
1	FLORENCE	4	5		0	0	0	0.000	0.14	3.026	49.36	3.4	42.2	13.82	55.97	96.0	300.0	PVC	0.5	71.3	1.0	78%	108%	1.06
J	FLORENCE	5	6		0	0	0	0.000	0.15	3.026	49.51	3.4	42.2	13.86	56.01	96.0	300.0	PVC	0.5	71.3	1.0	79%	108%	1.06

Notes:

- 1. Residential Average Flow of 350L/cap/day
- 2. Population Density (People/unit): Singles = 3.8, Semis = 3.8, Towns =3.5, Apartments = 3.0
- 3. Peaking Factor (M) = Harmon Formula  $(4.0 \text{ max}) = 1+(14/4+(\text{Population}/1000)^{1/2})$
- 4. Population Flow = Q(p) = (Population X 350L/day/person X Peaking Factor)  $\div$  86,400s/day
- 5. Infiltration Inflow = Q(i) = 0.28 L/sec/ha
- 6. Peak Flow = Q(d) = Q(p) + Q(i)

M:\2018\118201\DATA\Calculations\SAN\20210506 - SAN.xls\EVOY



APPENDIX D
Storm Sewer Design

PROJECT #: 118201 PROJECT NAME: HANNAN HILLS LOCATION: ALMONTE, ON.




#### 5 Year Storm Sewer Design Sheet

LOCAT	ION	A	REA (Ha)				FLOW	I					PROPOSE	D SEWER			
FROM	то	TOTAL AREA	R= 0.2	R= 0.65	INDIV 2.78 AR	ACCUM 2.78 AR	TIME OF CONC.	RAINFALL INTENSITY I	*PEAK FLOW Q (I/s)	PIPE SIZE (mm)	PIPE SLOPE (%)	LENGTH (m)	CAPACITY (I/s)	FULL FLOW VELOCITY (m/s)	TIME OF FLOW (min.)	EXCESS CAPACITY (I/s)	Q/Qfull
Α	В	1.26		1.26	2.28	2.28	20.00	70.25	159.95	450	0.40	108.0	180.50	1.13	1.59	20.55	0.89
В	С	1.31		1.31	2.37	4.64	21.59	66.95	310.91	600	0.40	135.0	388.73	1.37	1.64	77.82	0.80
D	E	1.05		1.05	1.90	1.90	20.00	70.25	133.29	450	0.40	105.0	180.50	1.13	1.54	47.21	0.74
E	С	1.13		1.13	2.04	3.94	21.54	67.04	264.07	600	0.40	107.0	388.73	1.37	1.30	124.66	0.68
С	POND				0.00	8.58	21.59	66.95	574.64	750	0.40	15.0	704.81	1.59	0.16	130.17	0.82
		4.750															

Definitions Q = 2.78 AIR Q = Peak Flow, in Litres per second (L/s) A = Area in hectares (ha) I = 5 YEAR Rainfall Intensity (mm/h) R = Runoff Coefficient

Notes:

- 1) Ottawa Rainfall-Intensity Curve 2) Min Velocity = 0.76 m/sec.
- 3) 5 Year intensity = 998.071 / (time + 6.053)<sup>0.814</sup>



Serviceability	and	Conceptual	SWM	Report

Hannan Hills

## APPENDIX E Conceptual Stormwater Management Design Memo



### MEMORANDUM

DATE: MAY 13, 2021 PROJECT: 118201

TO: ALEX MCAULEY

FROM: MELANIE SCHROEDER

RE: HANNAN HILLS SUBDIVISION

**CONCEPTUAL STORMWATER MANAGEMENT DESIGN** 

CC: MIKE PETEPIECE

The purpose of this memorandum is to provide details on the conceptual stormwater management (SWM) design for the proposed Hannan Hills Subdivision. Below is a review of the SWM criteria and presentation of conceptual stormwater water quality and quantity control for the site.

### **BACKGROUND**

The proposed Hannan Hills Subdivision is a 4.34 hectare (ha) site located in the Town of Almonte within the Municipality of Mississippi Mills, Ontario. The site is located to the north of the intersection of Florence Street and Adelaide Street. The existing land use consists of a single house surrounded by a lightly forested area. The site is adjacent to existing residential developments to the south of Florence Street and to the east of Adelaide Street.

### STORMWATER MANAGEMENT CRITERIA

The site is within the jurisdiction of the Municipality of Mississippi Mills and Mississippi Valley Conservation Authority (MVCA). The stormwater management criteria for the Hannan Hills Subdivision are as follows:

### Stormwater Quality Criteria:

 Provide an Enhanced level of water quality treatment corresponding to 80% long-term TSS removal.

### Stormwater Quantity Criteria:

 Control post-development peak flows to pre-development release rates for all storms up-to and including the 100-year event.

#### **EXISTING CONDITIONS**

The existing site is 4.34 ha and consists of a single house surrounded by a lightly forested area. The existing site drainage flows overland from southwest to northeast and discharges into the Almonte Municipal Drain. The front lots of the houses on the southwest side of Florence Street flow through the site to the Almonte Drain, resulting in an additional 0.58 ha of upstream drainage, for a total drainage area of 4.92 ha. The surficial soils consist of silty sand and glacial till (Hydrologic Soil



Group 'B') based on the Preliminary Geotechnical Investigation (Paterson Group, 2019). Refer to **Figure 2 – Existing Conditions Plan** for an aerial image of the existing site.

### PROPOSED CONDITIONS

The proposed conceptual site development consists of 2-storey townhouses and two residential blocks: one with stacked townhouses and the other with back-to-back townhouses. A proposed SWM block will contain a dry pond that will control post-development peak flows to pre-development levels. Water quality will be provided by means of a water quality treatment unit in conjunction with settlement in the dry pond.

The storm sewer system within the roadway will be sized to collect and convey the 5-year storm event to the pond. There will be a major drainage flow path within the roadways that will direct overland flow to the dry pond. Refer to **Drawing 118201-PGR** and **Figure 6 – Storm Servicing** for the conceptual grading and storm sewer layout.

The inlets, with inlet control devices (ICDs), to the storm sewers have been sized to convey the 5-year flow into the storm sewers. ICDs will be sized at the detailed design stage.

### **HYDROLOGIC & HYDRAULIC MODELING (PCSWMM)**

The PCSWMM model is a semi-lumped model that represents system flows from the development. The results of the analysis were used to simulate runoff from the site, size the dry pond for quantity control, and ensure the total peak flow leaving the site does not exceed pre-development levels. PCSWMM model schematics and model output are attached.

### Design Storms

Initial model runs were completed for the 1:100 year event using the 3-hour, 4-hour, and 6-hour Chicago distributions, and the 6-hour, 12-hour, and 24-hour SCS distributions to determine the critical storm event for the Site.

The 6-hour Chicago distribution (10-minute time step) was determined to generate the highest peak flows and storage volume within the post-development site and was selected as the critical storm distribution to be used in the analysis. The 4-hour Chicago storm distribution was used for the 25mm event (water quality event).

### Modeling Parameters

Hydrologic modeling parameters for each subcatchment were developed based on soil type, existing and proposed land use, and topography. Modeling parameters were determined as follows:

- Soil types were identified based on test pit data from the Preliminary Geotechnical Investigation (Paterson Group, 2019);
- Land use and ground cover were determined from satellite images and the proposed site layout;
- SCS Curve Numbers were assigned for the pre-development area based on the soil types and land use of the pervious areas:



- For the pre-development model, an area weighted CN value was used based on land cover. A CN value of 75 was used to represent good condition half acre rural residential lots with the hydrologic soil group (HSG) 'B' and a CN value of 60 was used to represent fair condition forest with the hydrologic soil group (HSG) 'B';
- For post-development conditions, the percentage of impervious area was determined for each subcatchment based on an approximate runoff coefficient of 0.65 based on townhouse land use. The percent impervious was determined using the following equation:

$$0 \text{ } \% \text{ } imp = \frac{C-0.2}{0.7}$$

- The "zero imperviousness" parameter represents the percent of the impervious area that has no depression storage (i.e., roof area);
- Equivalent width refers to the width of the subcatchment flow path.
- The hydrologic simulation uses depression storage to represent the amount of rainfall required to generate runoff from a catchment area;
  - Depression Storage (pervious areas): 4.67 mm;
  - Depression Storage (roads, driveways): 1.57 mm;
  - Depression Storage (rooftops): 0 mm.
- The simulation uses Manning's roughness coefficients (n) to represent the surface roughness for impervious and pervious land uses, open channels, and culverts. The model uses the following:
  - o Impervious areas (roadways, rooftops, paved areas): 0.015;
  - Pervious areas (grassed areas): 0.25;
- The simulation also uses Manning's roughness coefficients (n) to represent the roughness of the conduits that convey major and minor system flows. The model uses the following:
  - Concrete or PVC pipes: 0.013;
  - Roadways for overland flow: 0.015;
  - o Open channels: 0.035.

Refer to **Figure 118201-PSTM** for drainage areas. A detailed summary of model subcatchment parameters is attached.

### Dry Pond Sizing

Controlled runoff from the site will be directed to a proposed dry pond, which has been sized to control post-development peak flows to pre-development levels for storms up to and including the 100-year design event. The dry pond will also provide water quality treatment through a 24-hour to 48-hour drawdown time for the water quality event (4-hour 25 mm Chicago Storm event) and a low flow channel. Additional quality control will be provided by a water quality treatment unit located upstream of the pond inlet.

A summary of the pond design and storage volumes is provided in







**Table 1: Dry Pond Design Summary** 

Feature	Dry Pond
Side Slopes (H:V)	3:1
Bottom of Low Flow Channel (masl)	137.60
Bottom of Pond Elevation (masl)	137.85
Top of Pond Elevation (masl)	139.50
Bottom Area (m²)	963
Bottom Area (m²)	1,964
Storage Volume to Top of Pond (m³)	2,496

Outflows from the dry pond will be routed through an outlet structure designed to restrict flows to pre-development levels before outletting to the Almonte Drain. An emergency overflow spillway will be located along the northeast side of the pond, adjacent to the Almonte Drain and will allow for conveyance of events above the 100-year event.

The conceptual design for the dry pond outlet consists of:

- An 75 mm diameter orifice with an invert elevation of 137.60 m for the water quality event;
- A 250mm diameter orifice with an invert elevation of 138.30 m;
- A 0.8 m wide transverse weir with crest elevation of 138.85 m;
- An emergency overflow spillway with a crest elevation of 139.20 m.

The stage-storage-discharge table is provided in **Table 2**.

Table 2: Dry Pond Stage-Storage-Discharge (6-hour Chicago Storm Event)

Stage	Elevation (m)	Volume (m³)	Release Rate (L/s)
Outlet of Low Flow Channel	137.60	0	0
Inlet of Low Flow Channel	137.69	2	-
Bottom of Dry Pond	137.85	83	-
25mm Event	138.28	554	10
2yr Event	138.42	727	25
5yr Event	138.59	968	66
100yr Event	139.12	1,802	335
Top of Pond	139.50	2,496	-

### Model Results - Hydraulic Grade Line

Lots will need to be serviced with storm sump pumps due to the elevation of the pond outlet to the Almonte Drain. This will be evaluated using a hydraulic model of the proposed storm sewers during the detailed design stage.



### Model Results - Peak Flows

The PCSWMM model was used to evaluate pre- and post-development peak flows from the pond. The results of this analysis demonstrate that the proposed stormwater management strategy for the Hannan Hills Subdivision will control post-development peak flows to pre-development levels for all storm events up to and including the 100-year design event. The modelled peak flows are summarized in **Table 3**.

Table 3: Pre vs. Post-Development Peak Flows (6-hour Chicago Storm)

Scenario	Peak Flow (L/s)							
Scenario	25mm	2-year	5-year	100-year				
Pre-Development	10	39	93	346				
Post-Development	10	25	66	335				

### **CONCLUSIONS**

Post-development peak flows will be controlled to less than the pre-development peak flow rate for the 2-year through 100-year event. The dry pond will provide adequate storage for controlling the 100-year event to pre-development conditions. An Enhanced level of water quality treatment (80% long-term TSS removal) will be provided through a water quality treatment unit and the dry pond. The need for foundation drainage sump pumps will be analyzed in more detail at the detailed design stage.




### **ATTACHMENTS**

- Figures
  - Figure 2– Existing Conditions Plan
  - o Figure 6 Storm Servicing
  - o 118201-PSTM
  - o Figure 7 Conceptual Stormwater Management Facility
- Drawing
  - o 118201-PGR
- Model Subcatchment Parameters
- Theoretical ICD Sizing
- Model Schematics
  - o Pre-Development
  - o Post-Development
- PCSWMM Model Output Results
  - o Pre-Development
  - o Post-Development


### **MODELLING FILES**


Available and can be provided upon request:


- Packaged PCSWMM model
  - Pre-Development
  - Post Development




CUTAIVAZ DIVIC 270mm V422m









## Hannan Hills Subdivision (118201) **Pre-Development Model Parameters**



#### **Time to Peak Calculations**

(Uplands Overland Flow Method)

### **Existing Conditions**

		Overland Flow					Concentrated Overland Flow						Overall			
Area	Area	Length	Elevation	Elevation	Slope	Velocity	Travel	Length	Elevation	Elevation	Slope	Velocity	Travel	Time of	Time to	Time to
ID	(ha)	Lengui	U/S	D/S	Slope	Velocity	Time	Lengin	U/S	D/S	Slope	Velocity	Time	oncentratio	Peak	Peak
		(m)	(m)	(m)	(%)	(m/s)	(min)	(m)	(m)	(m)	(%)	(m/s)	(min)	(min)	(min)	(min)
R1	4.920	100	141.0	140.0	1.0%	0.25	6.67	200	140	137.0	1.5%	0.55	6.06	13	9	10

### **Weighted Curve Number Calculations**

Soil type 'B'

Area ID	Land Use 1	Area	CN	Land Use 2	Area	CN	Weighted CN
R1	Rural Residential	15%	75	Forest	85%	60	62

\*\*1/2 acre residential lots, woods fair

Silty sand/glacial till = soil type B

#### **Weighted IA Calculations**

Area ID	Land Use 1	Area	IA	Land Use 2	Area	IA	Weighted IA
R1	Rural Residential	15%	6.4	Forest	85%	12.7	11.7

# Hannan Hills Subdivision (118201) Post-Development Model Parameters



Area ID	Catchment	Runoff	Percent	No	Flow Path	Equivalent	Average
Alca ib	Area	Coefficient	Impervious	Depression	Length	Width	Slope
	(ha)	(C)	(%)	(%)	(m)	(m)	(%)
A1	0.310	0.65	64%	10%	34	9	2%
A2	0.950	0.65	64%	45%	45	21	2%
A3	1.240	0.65	64%	40%	50	25	2%
A4	0.270	0.65	64%	10%	34	8	2%
A5	0.750	0.65	64%	35%	67	11	2%
A6	1.120	0.65	64%	30%	64	18	2%
A7	0.280	0.20	0%	0%	21	13	2%

TOTAL: 4.92

### Hannan Hills Subdivision (118201) Conceptual PCSWMM Model - Orifice Sizing




**Equivalent Orifice Sizing** 


Inlet Name	Inlet / Outlet Node	Invert (m)	T/G (m)	CB Depth (m)	Area ID	Drainage Area (ha)	Static Ponding Depth (m)	Design Flow Rate <sup>1</sup> (L/s)	Artificial Orific Dia. <sup>2</sup> (m)	
2-year Inlet Capture Rate										
O-CB01	CB01	138.62	139.82	1.20	A1 & A2	1.26	0.25	265.2	0.338	
O-CB02	CB02	138.49	139.69	1.20	A3	1.24	0.25	258.7	0.334	
O-CB03	CB03	138.49	139.69	1.20	A6	1.12	0.25	228.8	0.314	
O-CB04	CB04	138.60	139.80	1.20	A4 & A5	1.02	0.25	209.3	0.301	
	7	<b>TOTAL</b>				4.64	-	962.0	-	


<sup>&</sup>lt;sup>1</sup> Design flow rate = 5-year peak flow based on PCSWMM model results (6-hour Chicago storm).


<sup>&</sup>lt;sup>2</sup> Theoretical orifice size based on design flow rate and estimated 1.2m CB depth.













ALTERNATIVE RUNOFF METHOD (ARM) - PCSWMM VERSION 7.3.3095

This is a new version of ARM – your feedback and suggestions are solicited. Create a ticket, post on the PCSWMM feature request forum, or email us directly!

 Simulation start time:
 1/25/2021 00:00

 Simulation end time:
 1/26/2021 00:00

 Runoff wet weather time steps:
 300 seconds

 Report time steps:
 60 seconds

 Number of data points:
 1441

Subcatchment	Runoff Method	Raingage	Area (ha)	Time of Concentration (min)	Time to Peak (min)	Time after Pea (min)
R1	Nash IUH	Raingage	4.92	13	8.67	61.33

ARM Runoff Summary

Subcatchment	Total	Total	Total	Total	Peak	Runoff
	Precip	Losses	Runoff	Runoff	Runoff	Coeff
	(mm)	(mm)	(mm)	10^6 ltr	LPS	(fraction)
R1	76.002	57.206	18.671	0.919	318.878	0.246

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.015)

\*\*\*\*\*\*\*\*\*\*\*\* Element Count \*\*\*\*\*\*\*

Raingage Summary

Name Data Source Data Recording Type Interval
Raingage C4hr-100yr INTENSITY 10 min.

\*\*\*\*\*\*\*\*\*\*\*\*\*
Node Summary

0.0214

0.0801

0.2945

0.4120

0.5296

0.6472

Transect 18mROW Area: 0.0137 0.0009 0.0034 0.0077 0.0308 0.0417 0.0530 0.0657 0.2240 0.2005 0.3180 0.2475 0.2710 0.3885 0.3650 0.4356 0.5531 0.4591 0.5766 0.4826 0.5061 0.6237 0.6001 0.6707 0.6942 0.7883 0.8588

	0.2524	0.2698	0.2847	0.2977	0.3093
	0.3240	0.3404	0.3578	0.3760	0.3948
	0.4140	0.4335	0.4532	0.4731	0.4932
	0.5133	0.5335	0.5538	0.5742	0.5945
	0.6149	0.6353	0.6557	0.6761	0.6965
	0.7169	0.7373	0.7577	0.7780	0.7983
	0.8186	0.8389	0.8591	0.8793	0.8995
	0.9197	0.9398	0.9599	0.9800	1.0000
Width:					
	0.0726	0.1453	0.2179	0.2905	0.3631
	0.4358	0.4721	0.5073	0.5776	0.6478
	0.7180	0.7882	0.8584	0.9287	0.9989
	0.9989	0.9990	0.9990	0.9990	0.9990
	0.9991	0.9991	0.9991	0.9992	0.9992
	0.9992	0.9993	0.9993	0.9993	0.9994
	0.9994	0.9994	0.9995	0.9995	0.9995
	0.9996	0.9996	0.9996	0.9997	0.9997
	0.9997	0.9997	0.9998	0.9998	0.9998
	0.9999	0.9999	0.9999	1.0000	1.0000

NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.

\*\*\*\*\*\* Analysis Options Process Models:
Rainfall/Runoff YES Rainfall/Runoff YES
RDII NO
Snowmelt NO
Groundwater NO
Flow Routing NO
Water Quality NO
Surcharge Method EXTRAN
Starting Date 01/25/2021 00:00:00
Ending Date 01/26/2021 00:00:00
Antecedent Dry Days 0.0
Report Time Step 00:01:00

Volume

Flow Routing Continuity	hectare-m	10^6 ltr
Dry Weather Inflow	0.000	0.000
Wet Weather Inflow	0.000	0.000
Groundwater Inflow	0.000	0.000
RDII Inflow	0.000	0.000
External Inflow	0.092	0.919
External Outflow	0.092	0.919
Flooding Loss	0.000	0.000
Evaporation Loss	0.000	0.000
Exfiltration Loss	0.000	0.000
Initial Stored Volume	0.000	0.000
Final Stored Volume	0.000	0.000
Continuity Error (%)	0.000	

Analysis begun on: Thu Apr 22 00:04:57 2021 Analysis ended on: Thu Apr 22 00:04:57 2021 Total elapsed time: < 1 sec

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.015)

WARNING 10: crest elevation raised to downstream invert for regulator Link O-CB01 WARNING 10: crest elevation raised to downstream invert for regulator Link O-CB04 WARNING 02: maximum depth increased for Node CB04

Element Count

 Number of rain gages
 1

 Number of subcatchments
 7

 Number of nodes
 23

 Number of links
 28

 Number of pollutants
 0

 Number of land uses
 0

Name Data Source Type Interval
Raingage C6hr-100yr INTENSITY 10 min.

Width %Imperv %Slope Rain Gage Outlet A1 A2 A3 A4 A5 0.31 90.87 64.30 64.30 2.0000 Raingage 2.0000 Raingage HP01 2.0000 Raingage 2.0000 Raingage 2.0000 Raingage 2.0000 Raingage 2.0000 Raingage 1.24 0.27 0.75 249.35 79.50 111.75 64.30 64.30 CB02 CB04 1.12 176.32 130.29 64.30 CB03 DryPond

\*\*\*\*\*\*\*\*\*\*\*\*
Node Summary
\*\*\*\*\*\*\*\*\*

Invert Max. Ponded External

Name	Туре	Elev.	Depth	Area	Inflow
CB01	JUNCTION JUNCTION JUNCTION	138.62	2.20	0.0	
CB02	JUNCTION	138.49	2.20	0.0	
CB03	JUNCTION	138.49	2.20	0.0	
CB04	JUNCTION	138.60	2.20	0.0	
HP01	JUNCTION	140.17	1.00	0.0	
HP02	JUNCTION	140.07	1.00	0.0	
HP03	JUNCTION	139.94	1.00	0.0	
HP04	JUNCTION	140.05	1.00	0.0	
HP05	JUNCTION	140.12	1.00	0.0	
HP06	JUNCTION	140.07	1.00	0.0	
AlmonteDrain	OUTFALL	137.50	0.38	0.0	
PondSpill	OUTFALL	139.00	0.00	0.0	
	STORAGE				
MH_outlet	STORAGE STORAGE	137.55	1.45	0.0	
MH01	STORAGE				
MH02		138.37			
MH03	STORAGE	138.22	1.98	0.0	
MH04		137.88			
MH05		137.81			
MH06	STORAGE	137.71	2.36	0.0	
		137.99			
		138.37			
MH09	STORAGE	138.85	1.35	0.0	

Name	From Node	To Node	Type	Length	%Slope	Roughness
MH01-02	MH01	MH02	CONDUIT	78.0	0.4103	0.0130
MH02-03	MH02	MH03	CONDUIT	39.0	0.3846	0.0130
MH03-04	MH03	MH 0 4	CONDUIT	86.0	0.3954	0.0130
MH04-05	MH 0 4	MH05	CONDUIT	16.0	0.4375	0.0130
MH05-06	MH05	MH06	CONDUIT	31.0	0.3226	0.0130
MH06-SWMF	MH06	DryPond	CONDUIT	15.0	0.7334	0.0130
MH07-06	MH07	MH06	CONDUIT	72.0	0.3889	0.0130
MH08-07	MH08	MH07	CONDUIT	95.0	0.4000	0.0130
MH09-08	MH09	MH08	CONDUIT	119.0	0.4034	0.0130
MHoutlet-Drain	MH outlet	AlmonteDrain	CONDUIT	12.0	0.4167	0.0130
MS01	HP01	CB01	CONDUIT	64.5	0.5426	0.0150
MS02	CB01	HP02	CONDUIT	48.6	-0.5144	0.0150
MS03	HP02	CB02	CONDUIT	61.4	0.6189	0.0150
MS04	CB02	HP03	CONDUIT	52.5	-0.4762	0.0150

MS05	HP05	CB04	CONDUIT
MS06	CB04	HP04	CONDUIT
MS07	HP04	CB03	CONDUIT
MS08	CB03	HP03	CONDUIT
MS09	CB03	HP06	CONDUIT
MS10	HP06	DryPond	CONDUIT
O-CB01	CB01	MH01	ORIFICE
O-CB02	CB02	MH03	ORIFICE
O-CB03	CB03	MH08	ORIFICE
O-CB04	CB04	MH09	ORIFICE
O-SWMF1	DryPond	MH outlet	ORIFICE
O-SWMF2	DryPond	MH outlet	ORIFICE
W1	DryPond	MH outlet	WEIR
W2	DryPond	PondSpill	WEIR

Cross Section Summary

Conduit	Shape	Full Depth	Full Area	Hyd. Rad.	Max. Width	No. of Barrels	Full Flow
MH01-02	CIRCULAR	0.45	0.16	0.11	0.45	1	182.63
MH02-03	CIRCULAR	0.45	0.16	0.11	0.45	1	176.83
MH03-04	CIRCULAR	0.60	0.28	0.15	0.60	1	386.10
MH04-05	CIRCULAR	0.60	0.28	0.15	0.60	1	406.16
MH05-06	CIRCULAR	0.60	0.28	0.15	0.60	1	348.76
MH06-SWMF	CIRCULAR	0.75	0.44	0.19	0.75	1	953.42
MH07-06	CIRCULAR	0.60	0.28	0.15	0.60	1	382.93
MH08-07	CIRCULAR	0.60	0.28	0.15	0.60	1	388.36
MH09-08	CIRCULAR	0.45	0.16	0.11	0.45	1	181.08
MHoutlet-Drain	CIRCULAR	0.38	0.11	0.09	0.38	1	113.18
MS01	18mROW	1.00	15.30	0.52	18.00	1	48297.78
MS02	18mROW	1.00	15.30	0.52	18.00	1	47024.54
MS03	18mROW	1.00	15.30	0.52	18.00	1	51580.03
MS04	18mROW	1.00	15.30	0.52	18.00	1	45244.17
MS05	18mROW	1.00	15.30	0.52	18.00	1	50946.08
MS06	18mROW	1.00	15.30	0.52	18.00	1	57952.40
MS07	18mROW	1.00	15.30	0.52	18.00	1	37818.88
MS08	18mROW	1.00	15.30	0.52	18.00	1	40261.00
MS09	RECT_OPEN	1.00	3.00	0.60	3.00	1	23856.62
MS10	RECT_OPEN	1.00	3.00	0.60	3.00	1	73445.11

53.0 0.6038 32.0 -0.7813 108.2 0.3327 66.3 -0.3771 18.0 -2.1116 3.0 145.0659

0.0150 0.0150 0.0150 0.0150 0.0130 0.0350

\*\*\*\*\*\*

Transect Summary

Transect	18mROW				
Area:					
	0.0009	0.0034	0.0077	0.0137	0.0214
	0.0308	0.0417	0.0530	0.0657	0.0801
	0.0962	0.1139	0.1333	0.1543	0.1770
	0.2005	0.2240	0.2475	0.2710	0.2945
	0.3180	0.3415	0.3650	0.3885	0.4120
	0.4356	0.4591	0.4826	0.5061	0.5296
	0.5531	0.5766	0.6001	0.6237	0.6472
	0.6707	0.6942	0.7177	0.7412	0.7648
	0.7883	0.8118	0.8353	0.8588	0.8824
	0.9059	0.9294	0.9529	0.9765	1.0000
Hrad:	0.3003	0.3231	0.3023	0.3700	1.0000
mad.	0.0188	0.0376	0.0564	0.0751	0.0939
	0.1127	0.1406	0.1767	0.2070	0.2318
	0.2524	0.2698	0.2847	0.2070	0.3093
	0.3240	0.2090	0.3578	0.2377	0.3948
	0.4140	0.4335	0.3376	0.3760	0.4932
	0.4140	0.4333	0.4532	0.5742	0.4932
	0.5133	0.5335			
			0.6557	0.6761	0.6965
	0.7169	0.7373	0.7577	0.7780	0.7983
	0.8186	0.8389	0.8591	0.8793	0.8995
	0.9197	0.9398	0.9599	0.9800	1.0000
Width:					
	0.0726	0.1453	0.2179	0.2905	0.3631
	0.4358	0.4721	0.5073	0.5776	0.6478
	0.7180	0.7882	0.8584	0.9287	0.9989
	0.9989	0.9990	0.9990	0.9990	0.9990
	0.9991	0.9991	0.9991	0.9992	0.9992
	0.9992	0.9993	0.9993	0.9993	0.9994
	0.9994	0.9994	0.9995	0.9995	0.9995
	0.9996	0.9996	0.9996	0.9997	0.9997
	0.9997	0.9997	0.9998	0.9998	0.9998
	0.9999	0.9999	0.9999	1.0000	1.0000

NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.

\*\*\*\*\*\*

```
Analysis Options
Flow Units ..... LPS
Process Models:
  Rainfall/Runoff ..... YES
  Antecedent Dry Days . 0.0
Report Time Step . 00:01:00
Wet Time Step . 00:05:00
Dry Time Step . 00:05:00
Routing Time Step . 2.00 sec
Variable Time Step . YES
Maximum Trials . 8
Number of Threads . 4
Head Tolerance . 0.001500
Head Tolerance ..... 0.001500 m
Depth
Runoff Quantity Continuity
                               hectare-m
                                                     mm
                                0.405
Total Precipitation .....
                                                 82.323
0.000
                                                 0.000
61.212
0.628
                                   0.301
Continuity Error (%) .....
                                  -0.783
                                  Volume
******
                                               Volume
10^6 ltr
Flow Routing Continuity
                               hectare-m
                                 0.000
Dry Weather Inflow .....
                                                  0.000
Wet Weather Inflow ......
Groundwater Inflow .....
                                   0.301
                                                  3.012
                                0.000
RDII Inflow ..... External Inflow .....
                                                  0.000
                                                  0.000
```

```
External Outflow .....
                                                                            3.018
Flooding Loss ......
                                                      0.000
                                                                            0.000
Exfiltration Loss .....
                                                       0.000
                                                                            0.000
Initial Stored Volume ....
                                                       0.000
                                                                            0.000
Continuity Error (%) .....
Time-Step Critical Elements
None
Highest Flow Instability Indexes
Link O-CB02 (2)
Link O-CB03 (1)
Link O-CB04 (1)
Link O-CB01 (1)
Routing Time Step Summary
Minimum Time Step
Average Time Step
Maximum Time Step
Percent in Steady State
                                                     2.00 sec
                                                     2.00 sec
                                                     0.00
Percent in Steady State : Average Iterations per Step : Percent Not Converging : Time Step Frequencies : 2.000 - 1.516 sec : 1.516 - 1.149 sec : 1.149 - 0.871 sec : 0.871 - 0.660 sec : 0.660 - 0.500 sec :
                                                     2 01
                                                     0.00
                                                   99.94 % 0.02 %
                                                     0.02 %
                                                     0.01 %
```

Subcatchment Runoff Summary

Subcatchment	Total Precip mm	Total Runon mm	Total Evap mm	Total Infil mm	Imperv Runoff mm	Perv Runoff mm	Total Runoff mm	Total Runoff 10^6 ltr	Peak Runoff LPS	Runoff Coeff
A1	82.32	0.00	0.00	18.94	52.18	10.97	63.15	0.20	136.71	0.767
A2	82.32	0.00	0.00	19.06	52.59	10.75	63.34	0.60	406.63	0.769
A3	82.32	0.00	0.00	19.12	52.56	10.66	63.23	0.78	524.73	0.768
A4	82.32	0.00	0.00	18.93	52.18	10.97	63.15	0.17	119.13	0.767
A5	82.32	0.00	0.00	19.31	52.57	10.39	62.97	0.47	305.81	0.765
A6	82.32	0.00	0.00	19.27	52.51	10.44	62.96	0.71	459.88	0.765
A7	82.32	0.00	0.00	53.88	0.00	29.39	29.39	0.08	74.18	0.357

Node	Туре	Depth	Depth	HGL	Occu	rrence	Reported Max Depth Meters
CB01	JUNCTION	0.11	1.52	140.14	0	02:14	1.52
CB02	JUNCTION	0.05	1.51	140.00	0	02:17	1.51
CB03	JUNCTION	0.05	1.47	139.96	0	02:22	1.47
CB04	JUNCTION	0.28	1.51	140.11	0	02:14	1.51
HP01	JUNCTION	0.00	0.08	140.25	0	02:10	0.08
HP02	JUNCTION	0.00	0.07	140.14	0	02:15	0.07
HP03	JUNCTION	0.00	0.06	140.00	0	02:18	0.06
HP04	JUNCTION	0.00	0.06	140.11	0	02:15	0.06
HP05	JUNCTION	0.00	0.08	140.20	0	02:10	0.08
HP06	JUNCTION	0.00	0.00	140.07	0	00:00	0.00
AlmonteDrain	OUTFALL	0.07	0.38	137.88	0	02:44	0.38
PondSpill	OUTFALL	0.00	0.00	139.00	0	00:00	0.00
DryPond	STORAGE	0.41	1.52	139.12	0	02:51	1.52
MH outlet	STORAGE	0.07	0.76	138.31	0	02:51	0.76
MH01	STORAGE	0.03	1.00	139.69	0	02:34	1.00
MH02	STORAGE	0.06	1.12	139.49	0	02:40	1.12
MH03	STORAGE	0.09	1.18	139.40	0	02:42	1.18
MH04	STORAGE	0.22	1.35	139.23	0	02:45	1.35
MH05	STORAGE	0.26	1.39	139.20		02:46	1.39
MH06	STORAGE	0.33	1.43	139.14	0	02:48	1.43
MH07	STORAGE	0.17	1.26	139.25	0	02:46	1.26
MH08	STORAGE	0.06	1.03	139.40	0	02:45	1.03
MH09	STORAGE	0.02	0.75	139.60	0	02:37	0.75

			Maximum				Total	
		Lateral	Total			Inflow		
						Volume		
Node	Type		LPS	-			10^6 ltr	
CB01	JUNCTION				02:10		0.804	
CB02	JUNCTION	524.73	525.20	0	02:10	0.784	0.841	-0.259
CB03	JUNCTION	459.88	460.10	0	02:10	0.705	0.765	-0.051
CB04	JUNCTION	305.81	421.36	0	02:10	0.472	0.652	0.167
HP01	JUNCTION	136.71	136.71	0	02:10	0.196	0.196	-1.058
HP02	JUNCTION	0.00	135.45	0	02:11	0		
HP03	JUNCTION	0.00	105.12	0	02:11	0	0.0398	0.000
HP04	JUNCTION	0.00	113.70	0	02:10	0	0.0356	2.774
HP05	JUNCTION	119.13	119.13	0	02:10	0.171	0.171	-0.961
HP06	JUNCTION	0.00	0.00	0	00:00	0		0.000 ltr
AlmonteDrain	OUTFALL	0.00	333.71	0	02:51	0	3.02	0.000
PondSpill	OUTFALL	0.00	0.00	0	00:00	0	0	0.000 ltr
DryPond	STORAGE	74.18	797.87	0	02:08	0.0823	3.02	0.004
MH_outlet	STORAGE	0.00	333.70	0	02:51	0	3.02	
MH01	STORAGE	0.00	209.71	0	02:02	0	0.745	
MH02	STORAGE	0.00	201.56	0	02:02	0		
MH03	STORAGE	0.00	425.20	0	02:05	0	1.55	
MH04	STORAGE	0.00	417.67	0	02:05	0	1.55	
MH05	STORAGE	0.00	410.61	0	02:05	0	1.55	
MH06	STORAGE	0.00	762.75	0	02:05	0		
MH07	STORAGE	0.00	377.12	0	02:08	0	1.38	
MH08	STORAGE	0.00	382.17	0	02:09	0	1.38	
MH09	STORAGE	0.00	176.74	0	02:09	0	0.615	-0.023

No nodes were surcharged.

No nodes were flooded.

Storage Unit	Average Volume 1000 m3	Avg Pcnt Full	Evap Pcnt Loss	Exfil Pcnt Loss	Maximum Volume 1000 m3	Max Pont Full	Occu	of Max rrence hr:min	Maximum Outflow LPS
DryPond	0.325	13	0	0	1.802	72	0	02:51	333.70
MH outlet	0.000	5	0	0	0.001	52	0	02:51	333.71
MH01	0.000	2	0	0	0.001	62	0	02:34	201.56
MH02	0.000	3	0	0	0.001	60	0	02:40	185.70
MH03	0.000	4	0	0	0.001	60	0	02:42	417.67
MH04	0.000	10	0	0	0.002	61	0	02:45	410.61
MH05	0.000	12	0	0	0.002	61	0	02:46	407.49
MH06	0.000	14	0	0	0.002	61	0	02:48	754.94
MH07	0.000	8	0	0	0.001	61	0	02:46	359.15
MH08	0.000	3	0	0	0.001	58	0	02:45	377.12
MH09	0.000	2	0	0	0.001	55	0	02:37	172.17

	Flow	Avg	Max	Total						
	Freq	Flow	Flow	Volume						
Outfall Node	Pcnt	LPS	LPS	10^6 ltr						
AlmonteDrain	76.67	23.13	333.71	3.018						
PondSpill	0.00	0.00	0.00	0.000						
System	38.34	23.13	333.71	3.018						

\_\_\_\_\_

Link	Type		Occu	of Max rrence hr:min		Full	Full
MH01-02	CONDUIT	201.56	0	02:02	1.34	1.10	1.00
MH02-03	CONDUIT	185.70	0	02:05	1.17	1.05	1.00
MH03-04	CONDUIT	417.67	0	02:05	1.58	1.08	1.00
MH04-05	CONDUIT	410.61	0	02:05	1.49	1.01	1.00
MH05-06	CONDUIT	407.49	0	02:05	1.48	1.17	1.00
MH06-SWMF	CONDUIT	754.94	0	02:06	2.09	0.79	1.00
MH07-06	CONDUIT	359.15	0	02:07	1.36	0.94	1.00
MH08-07	CONDUIT	377.12	0	02:08	1.61	0.97	1.00
MH09-08	CONDUIT	172.17	0	02:09	1.14	0.95	1.00
MHoutlet-Drain	CONDUIT	333.71	0	02:51	3.02	2.95	1.00
MS01	CHANNEL	133.01	0	02:10	0.47	0.00	0.19
MS02	CHANNEL	135.45	0	02:11	0.16	0.00	0.19
MS03	CHANNEL	78.27	0	02:15	0.20	0.00	0.19
MS04	CHANNEL	105.12	0	02:11	0.18	0.00	0.18
MS05	CHANNEL	116.07	0	02:10	0.46	0.00	0.19
MS06	CHANNEL	113.70	0	02:10	0.23	0.00	0.18
MS07	CHANNEL	38.57	0	02:15	0.13	0.00	0.16
MS08	CHANNEL	40.87	0	02:18	0.14	0.00	0.16
MS09	CONDUIT	0.00	0	00:00	0.00	0.00	0.13
MS10	CONDUIT	0.00	0	00:00	0.00	0.00	0.50
O-CB01	ORIFICE	209.71	0	02:02			1.00
O-CB02	ORIFICE	240.12	0	02:02			1.00
O-CB03	ORIFICE	210.00	0	02:09			1.00
O-CB04	ORIFICE	176.74		02:09			1.00
O-SWMF1	ORIFICE	12.35	0	03:44			1.00
O-SWMF2	ORIFICE	110.97	0	02:51			1.00
W1	WEIR	211.95	0	02:51			0.42
W2	WEIR	0.00	0	00:00			0.00

	Adjusted			Fraction of		Time	Time in Flow Class			
	/Actual	_	Up			Sup		Down		Inlet
Conduit	Length	Dry	Dry		Crit	Crit	Crit	Crit		Ctrl
MH01-02	1.00	0.01	0.00	0.00	0.99	0.00	0.00	0.00	0.88	0.00
MH02-03	1.00	0.00			0.99					
MH03-04	1.00	0.00	0.00	0.00	0.99	0.00	0.00	0.00	0.50	0.00

MH04-05	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.27	0.00
MH05-06	1.00	0.00	0.00	0.00	0.99	0.00	0.00	0.00	0.18	0.00
MH06-SWMF	1.00	0.00	0.02	0.00	0.98	0.00	0.00	0.00	0.11	0.00
MH07-06	1.00	0.00	0.00	0.00	1.00	0.00	0.00	0.00	0.39	0.00
MH08-07	1.00	0.00	0.00	0.00	0.99	0.00	0.00	0.00	0.67	0.00
MH09-08	1.00	0.00	0.00	0.00	0.99	0.00	0.00	0.00	0.64	0.00
MHoutlet-Drain	1.00	0.01	0.00	0.00	0.98	0.01	0.00	0.00	0.00	0.00
MS01	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.02	0.00
MS02	1.00	0.04	0.00	0.00	0.01	0.00	0.00	0.94	0.01	0.00
MS03	1.00	0.04	0.00	0.00	0.01	0.00	0.00	0.94	0.01	0.00
MS04	1.00	0.04	0.00	0.00	0.01	0.00	0.00	0.94	0.01	0.00
MS05	1.00	0.00	0.00	0.00	0.02	0.00	0.00	0.98	0.02	0.00
MS06	1.00	0.04	0.00	0.00	0.01	0.00	0.00	0.94	0.01	0.00
MS07	1.00	0.04	0.00	0.00	0.02	0.00	0.00	0.94	0.02	0.00
MS08	1.00	0.04	0.00	0.00	0.02	0.00	0.00	0.94	0.02	0.00
MS09	1.00	0.98	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00
MS10	1.00	0.01	0.99	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Conduit Surcharge Summary

Conduit		Hours Full Upstream		Hours Above Full Normal Flow	Hours Capacity Limited					
MH01-02	0.86	0.86	2.42	0.17	0.16					
MH02-03	2.42	2.42	3.66	0.18	0.19					
MH03-04	2.35	2.36	5.25	0.22	0.16					
MH04-05	5.25	5.25	6.22	0.03	0.01					
MH05-06	6.21	6.22	8.84	0.36	0.29					
MH06-SWMF	5.41	5.41	7.49	0.01	0.01					
MH07-06	4.25	4.25	8.84	0.01	0.01					
MH08-07	1.24	1.24	4.25	0.01	0.01					
MH09-08	0.63	0.63	2.39	0.01	0.01					
MHoutlet-Drain	0.24	0.87	0.24	1.42	0.24					

Analysis begun on: Thu Apr 22 16:31:35 2021 Analysis ended on: Thu Apr 22 16:31:39 2021 Total elapsed time: 00:00:04

APPENDIX F

<u>Excerpts From J.L. Richards Master Plan Update Report –</u>

<u>February 2018</u>

